

SOP-05

Site Handover Process

Department: Network Deployment & NOC Integration | Safaricom Ethiopia PLC | Version 2.1 | 2026

1. Purpose & Scope

Defines the formal acceptance criteria for integrating newly deployed base stations and network nodes from the Projects/Deployment team into live NOC operational custody.

2. Pre-Handover Requirements

- â€¢ Site Survey Report: completed and signed by deployment team.
- â€¢ Integration Test Report: all KPIs verified by RF/TX engineer.
- â€¢ Snag List: all outstanding items resolved or formally risk-accepted.
- â€¢ As-Built Documentation: rack layout, cable schedule, IP plan submitted.

3. Acceptance Testing Criteria

- â€¢ Cell availability must be 100% at time of handover.
- â€¢ VSWR < 1.5:1 on all antenna ports.
- â€¢ Pilot signal coverage verified per agreed drive test route.
- â€¢ Backhaul link quality: latency < 5ms, no packet loss.
- â€¢ Power system: commercial power connected, DG operational, UPS charged.

4. NOC Integration Steps

- â€¢ Add site to OSS/NMS network element manager and alarm system.
- â€¢ Configure alarm thresholds and notification routing in EMS.
- â€¢ Update network topology documentation and CMDB.
- â€¢ Assign site to appropriate regional cluster in NOC monitoring team.

5. Provisional Acceptance Period

- â€¢ 30-day provisional period following integration into NOC monitoring.
- â€¢ Deployment team remains responsible for defect rectification.
- â€¢ Any P1/P2 alarm on new site triggers automatic notification to PM.

6. Final Acceptance

- â€¢ Issue Final Acceptance Certificate after 30-day defect-free operation.
- â€¢ Site formally transferred to NOC Operations maintenance responsibility.
- â€¢ SLA clock starts from Final Acceptance Certificate date.